



Stair Type: Straight Staircase

Building Regulations: UK
Rise: 2700mm

Number of Risers: 13

Tread Type: Closed tread construction
String Material: 32mm Oak Engineered
Tread Material: 30mm Oak Treads

Riser Material: 9mm Oak Venered Risers

Individual Rise: 207.69mm
Going: 230.67mm
Overall String Width: 900mm
Nosing Style: Half Round

Top Right Newel: 90mm x 90mm Engineered Oak Bottom Right Newel: 90mm x 90mm Engineered Oak

Newel Type: PSE Newel

Newel Material: 90mm x 90mm Engineered Oak

Raking Handrail Right:

Landing Handrail Right:

Landing Handrail Right Length:

2000mm

Handrail Material: Pine With Oak Top Spindle Style: Stop Chamfered

Newel Caps:

Newel Cap Type: Oak Flat Cap Assembly: Assembled

Est. Delivery Date: from 25 Jan 21 to 27 Jan 21

Reference: STAIR 1

## Please note

- 1) Labour must NOT be booked until the staircase is delivered.
- 2) Your staircase will be put into production within 24 hrs of placing this order and will be produced according to this drawing.



Stair Type: Straight Staircase **Building Regulations:** UK 600mm Number of Risers: Tread Type: Closed tread construction 32mm Oak Engineered String Material: Tread Material: 30mm Oak Treads Riser Material: 9mm Oak Venered Risers Individual Rise: 453mm 200mm Going: 222.12mm Overall String Width: 900mm Nosing Style: Half Round Top sqht Newel: 90mm x 90mm Engineered Oak Botom Right Newel: 90mm x 90mm Engineered Oak Newel Type: **PSE Newel** New Material: 90mm x 90mm Engineered Oak Rak<mark>ing</mark> Handrail Right: Yes Landing Handrail Right: Landing Handrail Right Length: Yes 1000mm Handrail Material: Pine With Oak Top Spindle Style: Stop Chamfered **Newel Caps:** 900mm Newel Cap Type: Oak Flat Cap Assembly: Assembled Est. Delivery Date: from 25 Jan 21 to 27 Jan 21 STAIR 2 Reference:

## Please note

- 1) Labour must NOT be booked until the staircase is delivered.
- 2) Your staircase will be put into production within 24 hrs of placing this order and will be produced according to this drawing.