

Stair Type: Straight Staircase

Building Regulations: UK
Rise: 630mm

Number of Risers: 3

Tread Type: Closed tread construction

String Material: 32mm Redwood Pine (Furniture Grade)

Tread Material: 22mm MDF Treads
Riser Material: 9mm MDF Risers

Individual Rise:

Going:

Overall String Width:

Nosing Style:

Assembly:

210mm

233mm

1000mm

Half Round

Unassembled

Est. Delivery Date: from 24 Feb 21 to 26 Feb 21

Reference: Ref Poulter Stair 2

Please note


1) Labour must NOT be booked until the staircase is delivered.

2) Your staircase will be put into production within 24 hrs of placing this order and will be produced according to this drawing.



Stair Type: Straight Staircase

Building Regulations: UK
Rise: 630mm



Number of Risers: 3

Tread Type: Closed tread construction

String Material: 32mm Redwood Pine (Furniture Grade)

Tread Material: 22mm MDF Treads
Riser Material: 9mm MDF Risers

Individual Rise:210mmGoing:233mmOverall String Width:1000mmNosing Style:Half RoundAssembly:Unassembled

Est. Delivery Date: from 24 Feb 21 to 26 Feb 21

Reference: Ref Poulter Stair 3

Please note

475mm

1) Labour must NOT be booked until the staircase is delivered.

2) Your staircase will be put into production within 24 hrs of placing this order and will be produced according to this drawing.



Stair Type: Straight Staircase

Building Regulations: UK
Rise: 2100mm
Number of Risers: 10

Tread Type: Closed tread construction

String Material: 32mm Redwood Pine (Furniture Grade)

Tread Material: 22mm MDF Treads
Riser Material: 9mm MDF Risers

Individual Rise:

Going:

Overall String Width:

Nosing Style:

210mm

228mm

1000mm

Half Round

ď	10
LILLI OON	9
	8
	7
	6
	5
	4
	3
	2
	1
	1000mm

Top Left Newel:

Bottom Left Newel:

Newel Type:

90mm x 90mm Engineered Oak
90mm x 90mm Engineered Oak
PSE Newel

Newel Material: 90mm x 90mm Engineered Oak

Feature Tread: bullnose left

Feature Tread Material: 22mm MDF Treads

Assembly: Assembled

Est. Delivery Date: from 24 Feb 21 to 26 Feb 21

Reference: Ref Poulter Stair 1

Please note

1) Labour must NOT be booked until the staircase is delivered.

2) Your staircase will be put into production within 24 hrs of placing this order and will be produced according to this drawing.