



Stair Type:	Straight Staircase
Building Regulations:	UK
Rise:	2530mm
Number of Risers:	15
Tread Type:	Closed tread construction
String Material:	32mm Redwood Pine (Furniture Grade)
Tread Material:	22mm MDF Treads
Riser Material:	22mm MDF Risers
Individual Rise:	168.66mm
Going:	250mm
Overall String Width:	1200mm
Nosing Style:	Half Round
Assembly:	Assembled
Est. Delivery Date:	from 02 Mar 21 to 04 Mar 21
Reference:	HAND RAILS BY OTHERS

**Please note**

- 1) Labour must NOT be booked until the staircase is delivered.
- 2) Your staircase will be put into production within 24 hrs of placing this order and will be produced according to this drawing.